

**NORTHWEST PIPE FITTINGS, INC
OF SCOTTSBUFF, NE**

GAS VALVES

COMPUTER #	DESCRIPTION	
IRON BODY		
403-9684	10685B 1/2 IB GAS STOP	
403-7518	10685B 3/4 IB GAS STOP	
403-7526	10685B 1 IB GAS STOP	
403-7534	10685B 1 1/4 IB GAS STOP	
403-7542	10685B 1 1/2 IB GAS STOP	
403-7550	10685B 2 IB GAS STOP	
IRON BODY W/LOCK		
403-7604	10687B 1 IB GAS STOP	
403-7605	10687B 1 1/4 IB GAS STOP	



10685B



10687B

BRASS		
403-8030	10709 GBV 1/2 BALL GAS VALVE	
403-8032	10709 GBV 3/4 BALL GAS VALVE	



10709



Gas Valves

BrassCraft

A Masco Company

COATED GAS FLEX CONNECTORS

COMPUTER #	DESCRIPTION	LIST PRICE
401-6050	CSSC54-12 12" PROCOAT GAS FLEX CON. 1/2M	\$ 12.86
401-6052	CSSC54-24 24" PROCOAT GAS FLEX CON. 1/2M	\$ 18.90
401-6054	CSSC54-36 36" PROCOAT GAS FLEX CON. 1/2M	\$ 22.62
401-6056	CSSC54-48 48" PROCOAT GAS FLEX CON. 1/2M	\$ 32.72
401-6100	MAU1-10-8S 1/2" FIPXGAS CON FTG	\$ 3.74
401-6102	MAU2-10-8S 1/2" MIPXGAS CON	\$ 3.92



Connector Series**	Nominal Connector I.D. Inch	STRAIGHT LENGTH CAPACITY - BTU PER HOUR							
		12"	18"	24"	30"	36"	48"	60"	72"
CSSL-SSL CSST-SST	1/4	48,000	43,800	40,000	36,400	33,400	28,300	24,900	23,100
CSSD-SSD	3/8	102,000	93,100	85,000	77,100	71,100	60,500	53,200	49,100
CSSC-SSC	1/2	180,000	164,200	150,000	136,000	125,000	106,000	93,200	86,000
CSSB**	3/4	---	---	290,900	270,500	255,900	215,000	197,400	173,900

0.64 Sp Gr. 1000 BTU per Cu. Ft. (37.2 MJ/m³) gas at 0.5 inch water column (124Pa) pressure drop.
Per ANSI Z21.24 • CSA 6.10 for use with pressures not to exceed 1/2 PSI.

Connectors should be sized based upon the appliance gas consumption rate. Select a connector with a capacity equal to or greater than appliance input rate.

* The flow capacities in the above charts are the minimum performance criterion established in ANSI Z21.24 • CSA 6.10. The flow capacity of BrassCraft connectors, regardless of end fitting or valve (Safety +PLUS Excess Flow or Gas Ball) assembled, exceeds these minimum flow requirements.

